

Status: Open | see GS-02

[illegible]

The second-floor transfer beams SF-S06 (UC 305x305x158, x 6370) and SF-S08 (UC 356x406x287, x 12586) bear on the south wall (L2, top 174.975 AOD) directly over the 685-wide FF windows either side of the entrance bay. At TOS 175.229 the beam undersides are 6252 (S06) and 6185 (S08) above the slab datum; the architect's window head is 6023, leaving 229 mm (S06) and 162 mm (S08) of wall between head and beam. S-121 schedules an RCB152 x 300 - 2H16 lintel there, which would reach 6323, 71 mm into SF-S06 and 138 mm into SF-S08.

Please confirm the bearing detail: a steel spreader under each beam end (model assumption UC 152x152x30, 1285 long, 300 bearing each side, TOS = beam underside), or a revised lintel / beam arrangement. The window positions are the architect's and are held.

Name / date: _____

Status: Open | see GS-02

S-101 shows the stair void as the ellipse only (x 6.5-.12.4 m, y 2.2-.6.2 m) with a UC 203x203x46 trimmer on its north tangent (y -6.23 m, TOS 171.950, "WALL BELOW") and hollowcore north of it. The architect's two curved flights (19 risers each) continue north beside a 3.3 m slot and land on the first floor at y -8.9 m; that trimmer and the planks north of y 6.23 m would sit 1.1-1.5 m above the treads.

Please confirm the extent of the first-floor void (model: ellipse + flights + slot to y 8.93 m, planks HC-032/033/034 omitted, landing edge on the plank at y 8.89 m) and the trimmer arrangement around it.

Name / date: _____

Ref	Subject	Drawing	Status
EQ-01	SF-S06 / SF-S08 bearings over the FF windows FF-WF02 / FF-WF19 (S-102, S-121)	GS-02	Open
EQ-02	Stair void on S-101 vs the architect's main stair (Plan FF, Sections A-A / E-E)	GS-02	Open
EQ-03	RF-S13 lifting beam (UC 152x152x30) over the lift shaft - level and bearing	GS-02	Open
EQ-04	Roof steel levels (S-103 / S-200 / S-201) - for confirmation	GS-02	Open
EQ-05	RF-S40 / RF-S41 bay ridge beams land 244 mm above RF-S27 / RF-S28	GS-02	Open
EQ-06	Lintel depths vs the floor bearings (S-120 / S-121)	GA-01	Open
EQ-07	S-120 internal ICF walls flanking the hall (x 6.2 m / 12.4 m) - door positions	GA-01	Open

1. Questions raised on the ICF approval drawings against the structural engineer's drawing Tier Consult 078-TCE-DEN-XX-DR-S-096..210 rev -.
2. Each panel shows the engineer's drawing beside the architect's drawing and/or the ICF model, cropped to the same area.
3. Please answer in the response box of each question (or by email quoting the EQ reference); the approval drawings will be revised to suit.
4. EQ tags on the GA drawings link to these panels.

REV	DATE	DESCRIPTION
P01	23.09.26	Approval issue



PROJECT
Dendrons

QUESTIONS FOR THE ENGINEER

Structural queries on the ICF approval drawings - sheet 1 of 4

SCALE	SIZE	DATE	DRAWN
NTS	A3	23.09.26	TS

DRAWING No.


UKPCS-003-EQ-01

P01

EQ-03 RF-S13 lifting beam (UC 152x152x30) over the lift shaft - level and bearing

Status: Open | see GS-02

ICF model (GS-02)



ISSUE S-103 marks RF-S13 (UC 152x152x30, x 4225, y 7030..9373) as the LIFTING BEAM over the lift shaft; S-100 shows the shaft with UC 203x203x46 trimmers (2005 x 1925), S-101/S-102 the LIFT VOID and the STAIR VOID beside it, S-205 the blockwork shaft walls and the 200 pit recess. The model carries the blockwork shaft (walls x 3185..3385 / 5185..5385, y 7191..9145, 200 W/E, 100 N/S) and the secondary-stair enclosure west of it (x 2181..2385, to y 9925) from the architect's plans, up to the underside of the roof plateau steel (178.240 TOS). RF-S13 is modelled at TOS 175.229 (the second-floor level) bearing on the shaft's N and S walls.

QUESTION Please confirm the TOS of the lifting beam (175.229 as modelled, or at the roof plateau), its bearings on the blockwork shaft walls, the shaft wall thickness and the extent of the secondary stair (flight not modelled).


ENGINEER'S RESPONSE

Name / date:

EQ-04 Roof steel levels (S-103 / S-200 / S-201) - for confirmation

Status: Open | see GS-02

ICF model (GS-02)



ISSUE The model takes the mansard rafter underside from the wall plates (L2 top 174.975 + 75) rising at 45 degrees, matching the architect's sections within 40 mm; the plateau at the architect's 9330..9590 box (TOS 178.240) with knee purlins RF-S22/23 on the engineer's lines x 3084/15871 at the rafter underside (TOS ~178.0) and the y 4812 frame line as a purlin-type member (TOS 178.036). The S-200 A-A section reads ~500 mm low against these (eaves TOS 5996, plateau 9006). Two collinear pairs on the plateau (RF-S12/S14 and RF-S19/S20/S21) overlapped on the DWG and are modelled as UB203 middle pieces spliced to the UC254 cantilever ends over the posts.

QUESTION Please confirm the intended TOS of the cranked frames and knee beams, and the splice arrangement of the collinear plateau pairs.

ENGINEER'S RESPONSE

Name / date:

QUESTIONS REGISTER

QUERIES

Ref	Subject	Drawing	Status
EQ-01	SF-S06 / SF-S08 bearings over the FF windows FF-WF02 / FF-WF19 (S-102, S-121)	GS-02	Open
EQ-02	Stair void on S-101 vs the architect's main stair (Plan FF, Sections A-A / E-E)	GS-02	Open
EQ-03	RF-S13 lifting beam (UC 152x152x30) over the lift shaft - level and bearing	GS-02	Open
EQ-04	Roof steel levels (S-103 / S-200 / S-201) - for confirmation	GS-02	Open
EQ-05	RF-S40 / RF-S41 bay ridge beams land 244 mm above RF-S27 / RF-S28	GS-02	Open
EQ-06	Lintel depths vs the floor bearings (S-120 / S-121)	GA-01	Open
EQ-07	S-120 internal ICF walls flanking the hall (x 6.2 m / 12.4 m) - door positions	GA-01	Open

NOTES

- Questions raised on the ICF approval drawings against the structural engineer's drawing Tier Consult 078-TCE-DEN-XX-DR-S-096..210 rev -.
- Each panel shows the engineer's drawing beside the architect's drawing and/or the ICF model, cropped to the same area.
- Please answer in the response box of each question (or by email quoting the EQ reference); the approval drawings will be revised to suit.
- EQ tags on the GA drawings link to these panels.

REVISIONS

REV	DATE	DESCRIPTION
P01	23.09.26	Approval issue



CLIENT
ICF Homes

PROJECT
Dendrons

DRAWING TITLE

QUESTIONS FOR THE ENGINEER

Structural queries on the ICF approval drawings - sheet 2 of 4

SCALE	SIZE	DATE	DRAWN
NTS	A3	23.09.26	TS

STATUS	DRAWING No.	REV
FOR APPROVAL	UKPCS-003-EQ-01	P01

Status: Open | see GS-02

[illegible]

ENGINEER'S RESPONSE

Name / date:

Status: Open | see GA-01

Technical drawing of a wall section showing two columns. The drawing includes dimensions and labels for various components.

Dimensions:

- Top horizontal dimensions: 954, 4735, 953
- Left vertical dimensions: 724, 286
- Right vertical dimensions: 724, 286
- Bottom horizontal dimensions: 5930, 5941

Labels:

- EQ-06 (Red label on the left column)
- GF-WG08 (Green label in the center)
- GF-WG09 (Green label on the right)

The drawing shows a cross-section of a wall with two columns. The columns are labeled EQ-06 and GF-WG08. The wall is labeled GF-WG09. The dimensions are given in millimeters.

ENGINEER'S RESPONSE

Name / date:

Ref	Subject	Drawing	Status
EQ-01	SF-S06 / SF-S08 bearings over the FF windows FF-WF02 / FF-WF19 (S-102, S-121)	GS-02	Open
EQ-02	Stair void on S-101 vs the architect's main stair (Plan FF, Sections A-A / E-E)	GS-02	Open
EQ-03	RF-S13 lifting beam (UC 152x152x30) over the lift shaft - level and bearing	GS-02	Open
EQ-04	Roof steel levels (S-103 / S-200 / S-201) - for confirmation	GS-02	Open
EQ-05	RF-S40 / RF-S41 bay ridge beams land 244 mm above RF-S27 / RF-S28	GS-02	Open
EQ-06	Lintel depths vs the floor bearings (S-120 / S-121)	GA-01	Open
EQ-07	S-120 internal ICF walls flanking the hall (x 6.2 m / 12.4 m) - door positions	GA-01	Open

1. Questions raised on the ICF approval drawings against the structural engineer's drawing Tier Consult 078-TCE-DEN-XX-DR-S-096-.210 rev -.
2. Each panel shows the engineer's drawing beside the architect's drawing and/or the ICF model, cropped to the same area.
3. Please answer in the response box of each question (or by email quoting the EQ reference); the approval drawings will be revised to suit.
4. EQ tags on the GA drawings link to these panels.

REV	DATE	DESCRIPTION
P01	23.09.26	Approval issue



PROJECT	Dendrons
---------	----------

QUESTIONS FOR THE ENGINEER

Structural queries on the ICF approval drawings - sheet 3 of 4

SCALE	SIZE	DATE	DRAWN
NTS	A3	23.09.26	TS

DRAWING No.

REV


UKPCS-003-EQ-01

P01

EQ-07 S-120 internal ICF walls flanking the hall (x 6.2 m / 12.4 m) - door positions

Status: Open | see GA-01

ICF model (GA-01)



ISSUE S-120 shows ICF 286 mm walls either side of the hall with lintels at y 10.0-11.8 m and (S-121) 12.7-13.6 m; the model has these walls (Walls 43/44) with double doors GF-ID01/02 (1783 wide) and FF doors FF-ID01/02 (915) from the architect's swings. S-120 also shows lintels on the annex cross wall (Wall 46) at x 21.6-22.8, 23.5-24.5 and 26.9-27.8 m and on Wall 47 at y 5.05-6.87 m; the architect's plan shows the Wall 46 doors at 23.5-24.5 and 26.85-27.8 m and single doors at the north ends of Walls 45/47. Modelled to the architect (GF-ID03..07).

QUESTION Please confirm the door positions on the internal ICF walls.

ENGINEER'S RESPONSE

Name / date:

QUESTIONS REGISTER

QUERIES

Ref	Subject	Drawing	Status
EQ-01	SF-S06 / SF-S08 bearings over the FF windows FF-WF02 / FF-WF19 (S-102, S-121)	GS-02	Open
EQ-02	Stair void on S-101 vs the architect's main stair (Plan FF, Sections A-A / E-E)	GS-02	Open
EQ-03	RF-S13 lifting beam (UC 152x152x30) over the lift shaft - level and bearing	GS-02	Open
EQ-04	Roof steel levels (S-103 / S-200 / S-201) - for confirmation	GS-02	Open
EQ-05	RF-S40 / RF-S41 bay ridge beams land 244 mm above RF-S27 / RF-S28	GS-02	Open
EQ-06	Lintel depths vs the floor bearings (S-120 / S-121)	GA-01	Open
EQ-07	S-120 internal ICF walls flanking the hall (x 6.2 m / 12.4 m) - door positions	GA-01	Open

NOTES

1. Questions raised on the ICF approval drawings against the structural engineer's drawing Tier Consult 078-TCE-DEN-XX-DR-S-096..210 rev -.
2. Each panel shows the engineer's drawing beside the architect's drawing and/or the ICF model, cropped to the same area.
3. Please answer in the response box of each question (or by email quoting the EQ reference); the approval drawings will be revised to suit.
4. EQ tags on the GA drawings link to these panels.

REVISIONS

REV	DATE	DESCRIPTION
P01	23.09.26	Approval issue



CLIENT ICF Homes	PROJECT Dendrons
---------------------	---------------------

DRAWING TITLE QUESTIONS FOR THE ENGINEER Structural queries on the ICF approval drawings - sheet 4 of 4			
---	--	--	--

SCALE NTS	SIZE A3	DATE 23.09.26	DRAWN TS
--------------	------------	------------------	-------------

STATUS FOR APPROVAL	DRAWING No. UKPCS-003-EQ-01		REV P01